

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF LEELANAU  
RECEIVED FOR RECORD

1993 DEC 28 PM 4: 25

For corners in

<u>Leelanau</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>11W</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Barbara Kirt*  
REGISTER OF DEEDS

FILE #330

LIBER 2 PAGE 27

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Steven P. Bye, in a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-1: NW corner, Section 6: G.L.O. "Set post corner to towns 28-29N, Ranges 11-12W"  
Beech 20, S 89 W, 11 links  
Beech 22, S 82 E, 55 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1: NW corner, Section 6: Found 1/2" i.d. iron pipe with unreadable 5/8" cap, Wm. B. Batzer Jr previously found an axle shaft in pit of cobbles.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1: NW corner, Section 6: 1/2" i.d. iron pipe with unreadable 5/8" cap accepted by the Leelanau County Peer Group, November 29, 1993, and replaced with a 3/4" i.d. galvanized iron pipe 3' long with a brass cap.

- Power pole - S 05 E, 29.60'
- 23" maple - N 85 W, 68.07'
- 22" maple - East 57.31'
- Twin 8" pear - N 03 E, 59.68'



Signed by Steven P. Bye

Date 12-20-93

Surveyor's Michigan License No. 35991