

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

Sparta Twp.

1. Public Land Survey

T___ R___
T___ R___
T___ R___
T___ R___

2. Property Controlling
in Section

S___ 5 T___ 9N R___ 12W

Wit. Mon. on
N-S 1/4 line

3. Miscellaneous
Property in Sec.

S___ T___ R___
S___ T___ R___

1999 DEC 30 AM 9:20
"Other" #120
Rec Seq 2
11675
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Dec. 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Kent County Witness Monument, LCRC #10705

SW corner of steel farm building	S80°E	73.87'
SW corner concrete block farm building	N55°E	98.04'
NW corner barn foundation	N40°E	160.00'
Nail & KC Remon. tag W. side P. Pole	N25°E	65.96'
Capped Rerod (Bueche) - 0.07' West of line	North	88.77'
SE corner house siding	N60°W	97.83'
Nail & KC Remon. tag W. side P. Pole	S15°E	161.38'
In C/L N-S asphalt road ±		

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/24/98
CHAIRMAN Henry J. Fisher

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Kent County Witness Monument

All witnesses above OK

SURVEY &
REMONUMENTATION


MAY 22 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RESET Standard Kent County Witness Monument in MON. BOX

SW corner of steel farm building	S80°E	73.87'
SW corner concrete block farm building	N55°E	98.04'
NW corner barn foundation	N40°E	160.00'
Nail & KC Remon. tag W. side P. Pole	N25°E	65.96'
Capped Rerod (Bueche) - 0.07' West of line	North	88.77'
SE corner house siding	N60°W	97.83'
Nail & KC Remon. tag W. side P. Pole	S15°E	161.38'
In C/L N-S asphalt road ±		



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 12/28/99