

LIBER

1 PG 1121

STATE OF MICHIGAN
COUNTY OF KALAMAZOO
RECEIVED FOR RECORDLAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 MAR 17 PM 3 39


For corners in ROSS TWP.

KALAMAZOO
(County)

Located In:

Corner Code #

1. Public Land Survey T 1 S R 9 W I-4
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R


CLERK-REGISTER

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Randy B. Ligman in a field survey on January 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:

1880's - F. Hodgeman C.S. Placed Clay Tile post during official Township Remonumentation.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found top section of Clay Tile leaning West against concrete fence corner base, found bottom section of Tile with stones around. Reset top section over bottom section.


 **RATIFIED**
BY KALAMAZOO COUNTY
REMONUMENTATION
PEER GROUP
3-3-94



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Clay Tile is accepted as a careful and faithful perpetuation of the original corner. Placed Standard Sleeve over existing Clay Tile, accessories:

Nail & Tab in West face of	7" Oak N. 10 deg. W.	35.03'
Nail & Tab in Northeast face	8" Oak N. 50 deg. W.	15.52'
Nail & Tab in South face	14" Oak WEST	38.55'
Nail & Tab in West face	36" Oak S. 15 deg. E.	8.64'

Signed by  Date 3/16/94Surveyor's Michigan License No. 28413