

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:12

For corners in
LIVINGSTON
(County)

Located in: GREEN OAK Corner Code #

9

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

- 1. Public Land Survey T 1N R 6E H-5
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

LSC# 1151m

Register of Deeds Stamp and File Number

I, Bryan L. Boss, in a field survey on OCT. 12, 1999

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


SET POST
24" WHITE OAK N22° W 31 L
12" WHITE OAK S. 26 1/2° E 47L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT WITH ALUMINUM CAP IN FENCE
RUNNING EAST-WEST IN OLD GRAVEL PIT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONCRETE MONUMENT WITH ALUMINUM CAP IN EAST/WEST FENCE. SET CARSONITE MARKER AS GUARD STAKE
N 70°E 65.50' SET REMON N/T SE/SIDE BROKEN OFF POLE
S 40°E 50.63' SET REMON N/T N E/SIDE 6" CEDAR
DUE SOUTH 120.30' SET REMON N/T WEST SIDE 18" LOCUST
DUE EAST 100.00' FOUND DNR CONCRETE MONUMENT



PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 7-21-99 CO. REP JED

Signed by Bryan L. Boss
Surveyor's Michigan License No. 29238

Date NOV. 3, 1999