

MAR 29 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remenumentation  
Peer Group Under Act 345 Of  
P.A. Of 1996 On 10/11 1999  
Mr. David R. G. S.  
Chairman

For corners in  
MENOMINEE SECTION

Located In: Corner Code #

- |                                       |                             |       |
|---------------------------------------|-----------------------------|-------|
| 1. Public Land Survey                 | T <u>38</u> N R <u>26</u> W | E-5   |
|                                       | T ___ R ___                 | _____ |
|                                       | T ___ R ___                 | _____ |
|                                       | T ___ R ___                 | _____ |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___           | _____ |
|                                       | S ___ T ___ R ___           | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___           | _____ |
|                                       | S ___ T ___ R ___           | _____ |

BK. 6 Pg. 90  
RECEIVED FOR RECORD  
28 DEC 1999 3:56:09 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Jan., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by George E. Adair - B.T.'s - Cedar, 12" - N74°W - 12 lks.; Cedar, 18" - S17°E - 32 lks. All original evidence for this corner has been destroyed by years of decay.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The double proportional position for this corner was determined by measurement between the NW Corner of Section 9, the S1/4 Corner of Section 9, the SW Corner of Section 8 and the E1/4 Corner of Section 17. Using this position, we found the distance to the Little Cedar River to be 535 feet (GLO = 516 feet) and the distance to a Brook to the South to be 495' (GLO = 495'). We accepted the double proportional location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" dia. x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner.

- |                        |       |            |          |
|------------------------|-------|------------|----------|
| 5" dia. White Ash      | S47°E | 17.53 feet | Scr. NBT |
| 7" dia. Elm            | S65°W | 26.20 feet | Scr. NBT |
| 6" dia. White Ash      | N14°W | 16.69 feet | Scr. NBT |
| Metal Survey Sign Post | East  | 1.25 feet  |          |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca 26461  
Surveyor's Michigan License No. \_\_\_\_\_

Date Dec. 18, 1999