

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 19827 PAGE 755
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
04/13/1999 01:46:43 P.M. RECEIPT# 18471
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABELL, CLERK/REGISTER OF DEED

For corners in

Oakland

(County)

Located In: Pontiac Corner Code # E-6
Twp.

1. Public Land Survey

T 3NR 10E E-6

T R

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Compliance with
ACT 348, P.A. 1990
APPROVED ON: 3-18-99 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____


I, Raymond J. McCoy in a field survey on Feb. 24 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Wampler, D.S. Set Post
There are NO L.C.R.C.'s recorded.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No corner was found. Set corner by using monumentation in "HIGHWOOD SUBDIVISION (L.21, Pg. 32, 1920). More particularly using the North line of Lots 62-67 and the line formed between the S.W. corner of Lot 152 to the S.W. corner of Lot 440. Corner falls 5ft. South of the centerline of Columbia Ave.

State Plane Coordinates N 428227.1828
E 13412769.9686

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x24" iron rod with 2" diameter brass disk stamped Oakland County Remonumentation P.S. #21270 in a New Monument Box.

Witnesses:
S 61° W, 81.63' Set O.C.R.T. #21270 in N.W. face of Power Pole.
N 70° W, 127.38' Set O.C.R.T. #21270 in N.E. face of Light Pole.
N 61° E, 80.66' Set O.C.R.T. #21270 in S.E. face of traffic support pole.
S 61° E, 80.37' Set O.C.R.T. #21270 in N.E. face of Traffic support pole.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Raymond J. McCoy
Surveyor's Michigan License No. 21270

Date March 18 1999