

NOV 21 1997

LIBER 2 PAGE 144

RECEIVED FOR RECORD

COMMISSION

REMOUNUMENTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 SEP -9 AM 8:58
LIBER NO. 2 PAGE NO. 144
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T 10N R 13E	G - 1
	T R	
	T R	Log-2
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A Milletics, in a field survey on June 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G - 1
GLO Notes
Intersect 29 Links West
Birch 16, S13W 30
Birch 7, S45 1/2 E 38


APPROVED PEER BOARD MEETING
Aug 18, 1997 JM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 1
Found Monu Box - removed by Sanilac Co. Road Comm. during reconstruction of road, REPLACED using Act 74 recording Liber 1 Page 380

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 1
NW Corner Section 3 T10N-R13E
Monu Box Set with iron & cap
East 20.05 to the SE cor Section 32 T11N-R13E Monu Box
N45°W 83.70 to SE Cor of a Bldg
S45°W 69.00 to a nail in a Power Pole
N45°E 82.36 to a nail in a Power Pole
S45°E 61.47 to a Riser Box
East 2639.06 to the N 1/4 Cor Section 3



Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Aug 11, 1997