

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 28477 PAGE 224

PC-555SW Page 1

For corners in  
Wayne  
County

1. Public Land Survey

Located in: MONGUAGON  
OTHER  
Corner Code  
GROSSE ILE  
PC-555SW  
#004  
Seq. #2  
Pg 709

2. Property Controlling  
In Section  
3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LIBER 28647 PAGE 709

Compliance with  
ACT 345, P.A. 1990APPROVED ON: 11-30-95 DPL  
WAYNE COUNTY REMONUMENTATION  
PRIVATE CLAIMS COMMITTEE

Register of Deeds Stamp and File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kenneth S. Wilkerson in a field survey on 12/04/1995  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
required in the current manual of survey Instructions of the United States Department of the  
Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner  
points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan  
Board of Land Surveyors or by a Decree of a Court of Law, established, re-established,  
monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be  
recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

01/01/1805 GREELEY

ON THIS DATE  
NO WITNESSES

SET POST

96065624

952731884-7 AM

(Witnesses Continued on Back ...)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

REESTABLISHED SW CORNER OF PRIVATE CLAIM 555 BY SUPERVISORS PLAT NO. 43 L.64,  
P.99 & GROSSE ILE MANOR L.58 P.89

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12/04/1995 WILKERSON 21485 O.H.M. REMON


SET 1/2" IRON ROD IN GRASSY AREA WITH W.C.R. CAP  
CORNER FALLS INTO THE DETROIT RIVER

- 1 SET P.K. NAIL IN JOINT CO CONC. RETAINING WALL N55W 10.45'
- 2 P.K. NAIL IN N. STEM OF TWIN 6" APPLE S20E 13.98'
- 3 N.E. COR OF BRIDGE S21W 32.64'
- 4 P.K. SET IN WALK N. SIDE OF BRIDGE S35W 43.83'

\$ 10.00 DEED  
21 DEC 95 9:21 A.M. RECEIPT# 58  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

\$ 4.00 REMONUMENTATION

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as  
the best available evidence of the position of the original corner.

Signed by   
Drafted by Kenneth S. Wilkerson


Surveyor's Michigan License No. 21584

Orchard, Hiltz and McClellan, Inc. 34935 Schoolcraft Road Livonia, MI 48150

RECORDED TO ADD PEER GROUP DATE

Date

DEC 13 1995



RF-RECDON

REC  
PC  
P.C.

100  
100