

RECEIVED

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1995 NOV 13 PM 4:27

For corners in **COMMISSION**  
WEXFORD

*Linda Laughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
	21N 11W	M-6
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **CRAIG J. PULLEN**, in a field survey on **OCTOBER 5**, 19**95**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- M-6 1837 G.L.O. SURVEY BY J. BRINK WOOD POST BEECH 7 N31½W 51 SUGAR 10 S49½W 27
- 1902 D.E. TEED SURVEY IN SEC.18, T21N, R10W FOUND STAKE BUT AM NOT CERTAIN ABOUT WIT. TREES ALTHOUGH THINK I FOUND SOME REMAINS OF SUGAR ROOTS SW SUGAR 14 S54W 53 SUGAR 20 S80W 45
- 1965 ROAD COMMISSION WITNESS BOOK 1" PIPE USFS COR. MARKER W 15.90' FENCE COR. E 27.60'
- 1973 J. ERICKSON, PS #16929 L.C.R.C. L2, P.552 FOUND ½" PIPE IN CENTERLINE N-S ROAD AND IN LINE WITH FENCE TO EAST. REPLACED WITH WEXFORD COUNTY MONUMENT. N50°E 27.64' 16" MAPLE S40°W 42.76' 14" MAPLE S30°E 47.72' 10" MAPLE IN CLUMP
- 1975 J.L. WILCOX & ASSOC. SURVEY L.1, P.354 AND L.C.R.C. L2, P.776 BY J.L. WILCOX, PS #14102. FOUND STANDARD WEXFORD COUNTY MONUMENT S25°E 8" MAPLE 47.62' S40°W 10" DBL. MAPLE 42.76' N50°E 14" MAPLE 27.57'
- 1990 WADE-TRIM/GRANGER SURVEY BY J. RAY, PS #25869 DATED 10-25-90 FOUND WEXFORD COUNTY MONUMENT S25°E 8" MAPLE 47.62' S40°W 10" DOUBLE MAPLE 42.76' N50°E 14" MAPLE 27.57' EAST ½" IRON 33.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-6 FOUND WEXFORD COUNTY MONUMENT IN POOR CONDITION IN CENTERLINE OF 25 ROAD AND IN LINE WITH OLD FENCE TO EAST AND FOUR PREVIOUS WITNESSES. REPLACED WITH 5/8" X 36" IRON WITH BRASS CAP. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved

Date: 10 Nov 95  
*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 ¼ CORNER COMMON TO SECTION 13, T21N, R11W, AND SECTION 18, T21N, R10W
- 5/8" X 36" IRON AND BRASS CAP STAMPED: CJP, 39095, ¼, 13, 18, 1995
- S25°E 8" MAPLE 47.62'
- S40°W 10" DOUBLE MAPLE 42.65'
- N50°E 14" MAPLE 27.57'
- EAST ½" IRON 33.00'



Signed by *Craig J. Pullen*  
Surveyor's Michigan License No. 39095

NOVEMBER 9, 1995