

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 47N R 17W	G8
	T 47N R 17W	G10
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G8 03/15/2012 and G10 04/19/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G8) Quarter corner common to Sections 21 and 22. 1958 - Reestablished by Billy D. Buckler RLS midway and on line between two Section corners. Set 1" pipe with 4" brass cap. 12" H.Maple S38E 54 links, 7" H.Maple S80W 49 links, 11" Y.Birch N68E 55 links.

(G10) Quarter corner common to Sections 27 and 28. 1960 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" pipe with 4" brass cap. 8" Forked Beech S32W 32.5 links, 6" W.Birch N38W 47 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G8) The 1958 monument was recovered as described, in good condition and at record bearing and distance from the 1958 witnesses. The H.Maple NBTs are in good condition. The Y.Birch NBT is now a stump. Found the monument to be 0.66' east and 1.25' north of the record position midway between Section corners and I accepted same as a careful and faithful reestablishment of the position of the original corner.

(G10) Found the 1960 monument in good condition and at record bearing and distance from the stump remains of the 1960 witnesses. Found the monument to be 0.47' east and 2.19' north of the record position midway and on line between Section corners and I accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G8) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap.
 Set measuring nail with MDNR tag in the side of:
 15" Sugar S35E 36.6' mrkd "1/4S" 1958 NBT
 12" Sugar S87W 32.45' do do
 8" twin Sugar N60E 5.75' mrkd "1/4S NBT"
 10" Sugar N45W 23.2' do
 Bearings are magnetic.

(G10) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap.
 Set measuring nail with MDNR tag in the side of:
 8" Maple S87W 22.9' mrkd "1/4S NBT"
 6" Maple N59W 48.25' do
 7" Maple S26W 2.15' do
 15" twin Maple N53E 44.2' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/26/2012

For the Michigan Department of Natural Resources, Forest Resources Division

