

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 17W	I2
	T 47N R 17W	I3
	T	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on I2 07/30/13 do hereby state  
I3 08/06/13  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I2) Quarter corner common to Sections 2 and 3. 1956 - Remonumented by Billy D. Buckler RLS at  
record bearing and distance from one Hemlock B.T. in poor condition. Set 1" ID iron pipe with 4"  
brass cap. 10" Hard Maple N87°W 32 links, 8" Soft Maple N40°E 19 links.

(I3) Corner common to Sections 2-3-10-11. 1956 - Billy D. Buckler RLS reestablished by double  
proportionate measurement to the original record between corners 1 mile E,W,S and 1/2 mile N. Set  
1"ID iron pipe with 4" brass cap. 14" Hard Maple N69°E 27 links, 14" Hard Maple N33°W 78 links, 7"  
Hard Maple S05°W 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I2) Found the 1956 monument in good condition and at record bearing and distance from the 1956  
witnesses. The Hard Maple is in good condition, the Soft Maple is now a stump. Accepted the  
monument as a careful and faithful perpetuation of the position of the original corner.

(I3) Found the 1956 monument in good condition and at record bearing and distance from the 1956  
witnesses. The Hard Maples NE and NW are now stumps; the Hard Maple SW is in good condition.  
Checked distances to corners 1 mile south and 1/2 mile north and found I3 to be substantially at the  
record position with respect to these two corners. Accepted the monument as a careful and faithful  
reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I2) Found 1"ID I.pipe with 4" brass MI Dept. of  
Conservation cap. Set measuring nail with MDNR tag  
in the side of:  
12" Sugar N85°W 21.2' mrkd "1/4S" 1956 NBT  
18" Maple S49°W 5.0' "1/4S NBT"  
16" Maple N02°W 6.7' do  
9" Sugar N84°E 42.1' do  
E= 8045529.350 N= 190854.671

(I3) Found 1"ID I.pipe with 4" brass MI Dept. of  
Conservation cap. Set measuring nail with MDNR  
tag in the side of:  
16" Sugar S09°W 12.2' mrkd "S10" 1956 NBT  
7" Sugar S63°E 11.65' "S11 NBT"  
4" Sugar N64°W 15.0' "S3 NBT"  
6" Sugar N36°E 31.35' "S2 NBT"  
E= 8045536.998 N= 190047.955

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)  
Coord. Ref.=NGS PID DJ8902: N= 177197.949 m. E= 8027768.701 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 08/29/2013

For the Michigan Department of Natural Resources, Forest Resources Division

