

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 17W	J3
	T 47N R 17W	J1
	T	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on J3 07/29/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner between Sections 2 and 11. 1956 - Billy D. Buckler RLS reestablished the corner
position midway and on line between Section corners east and west. Set 1"ID iron pipe with 4" brass
cap. 14" Hard Maple N27°W 58 links, 9" Soft Maple N73°E 12 links.

(J1) Quarter corner common to Section 2 T47N-R17W and Section 35 T48N-R17W. 1960 - Billy D. Buckler
RLS reestablished the corner position midway and on line between Section corners east and west. Set
1"ID iron pipe with 4" brass cap. 6" Soft Maple S39°W 14 links, 8" Elm N81°E 33 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) Found the 1956 monument in good condition and at record bearing and distance from the 1956
witnesses. The Hard Maple NW is standing dead. The Soft Maple NE is in good condition. Found the
monument to be substantially at the position of record between Section corners and accepted same as
a careful and faithful reestablishment of the position of the original corner.

(J1) Found the 1956 monument in good condition and at record bearing and distance from one remaining
1956 witness: The Soft Maple SW is now a stump. The Elm NBT was not recovered. Found the monument
to be substantially at the position of record between Section corners and accepted same as a careful
and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Found 1"ID I.pipe with 4" brass MI Dept. of
Conservation cap. Set measuring nail with MDNR tag
in the side of:
14" Maple N77°E 8.05' mrkd "1/4S" 1956 NBT
12" Sugar S38°E 21.85' "1/4S NBT"
12" Maple S43°W 13.75' do
8" Maple N50°W 21.3' do
E= 8046339.723 N= 190050.246

(J1) Found 1"ID I.pipe with 4" brass MI Dept. of
Conservation cap. Set measuring nail with MDNR
tag in the side of:
7" Sugar S88°W 10.1' mrkd "1/4S NBT"
13" Sugar S04°W 15.9' do
14" Sugar N65°E 13.3' do
11" Sugar N11°W 26.8' do
E= 8046325.862 N= 191655.346

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID DJ8902: N= 177197.949 m. E= 8027768.701 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/29/2013

For the Michigan Department of Natural Resources, Forest Resources Division

