

FEB 23 1999

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 12/16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

05-112

For corners in

Alger
(County)

Located In:

Corner Code #

1. Public Land Survey

T50N R13W

111-12 #3

2. Property Controlling
in Section

S

T

R

3. Miscellaneous
Property in Sec.

S

T

R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

TIME 10:00 A.M.

JAN 8 1999

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on October 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

111-12: P.L.S. - Francis Colman, DS, 1851. Intersect Lake Superior and set meander post. Y. Pine 12, S.58°E., 38 links, W. Pine 12, S.71°W., 100 links. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

111-12: Witness corner to meander set on section line extended from South at 205.1 feet North of quarter corner. Record = 529.3 feet. Erosion has moved bluff inland 294 feet. Set monument and established new reference trees. Corner as Monumented is accepted as a careful and faithful witness to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

111-12: Set witness corner, Berntsen aluminum monument no. AINB30, stamped to locate and identify witness corner position - 324.2 feet South of meander corner position. Established the following reference trees with BT signs, blazed and scribed. Set PK nails for measure with aluminum I.D. washers in the following. * White Pine 14", S.84°W., 29.76 feet, "BT", * White Pine 6", S.37°W., 31.21 feet, "BT", * Red Pine 12", S.41°E., 18.47 feet, "WC BT", * White Pine 14", N. 72°E., 28.39 feet. Survey marker sign on 6 foot steel post, East, 1.0 feet. Corner is 30 feet South of top of bluff. All bearings are magnetic.


Signed by

Robert L. Jamros

Date

December 16, 1998

Surveyor's Michigan License No.

25849

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1971

REVISED JAN. 1981

REVISED OCT. 1991