

SURVEY & REMONUMENTATION

FEB 03 1998

1997 ALPENA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Alpena
(County)

Located In:

Corner Code #

Liber 000002 Page 0081

STATE OF MICHIGAN
County of Alpena
Recorded
08-06-1997 10:45:08
Kathy J. Matash
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | | | | |
|------------------------------------|---|-----|---|----|-----------------------------|
| 1. Public Land Survey | T | 30N | R | 5E | L-5, (S $\frac{1}{4}$, 12) |
| | T | | R | | Green Twp. |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous | S | | T | | |
| Property in Section | S | | T | | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on May 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey by Lewis Clason - Set post & referenced: (Beech 8 N58E 72, Do 10 S60W 42).
- 1894: County Survey by Wm. LeRoy - Set stake 4" sq. & referenced.
- 1907 & 1929: County Survey by Wm. LeRoy - Visited corner.
- 1974: L.C.R.C. Liber 1 Page 49 by Delmer Porter - Fd. 1/2" Pipe and referenced.
- 1994: Survey Field Notes by Farrier Surveying - Found 1/2" iron pipe bent.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997: Found 1/2" iron pipe and 3 witnesses as per 1974 L.C.R.C. by Delmer Porter.

The position of this corner is compatible with county and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 ALPENA COUNTY
PEER APPROVED 6/19/97


D. J. B. Cur

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997: Set 3" dia. aluminum cap, stamped to identify the corner, over 1/2" iron rod in place of and after removing 1/2" iron pipe.

Reestablished witnesses are:

- Steel Fe. Post - S10E - 28.27'
- 11" Blazed Maple - N20E - 41.49'
- 15" Blazed Maple - N46W - 45.38'
- 14" Ash - S30W - 64.82'



Signed by Thomas L. Fabis

Date July 31, 1997

Surveyor's Michigan License No. 31591