

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| Baraga<br>(County)                    | Located In: | Corner Code #       |
|---------------------------------------|-------------|---------------------|
| 1. Public Land Survey                 | T 48N R 32W | G4<br>(GCDB 400540) |
| 2. Property Controlling<br>in Section | S T R       |                     |
| 3. Miscellaneous<br>Property in Sec.  | S T R       |                     |
| 4. Lot No. , Recorded Plat            |             |                     |
| 5. Private Claims                     |             |                     |

Register of Deeds Stamp & File Number

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Stephan J. Szyszkoski, in a field survey on 05/22/14 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 9 and 10. 1852 - Established by Guy Carleton, Deputy, midway and  
on the Section line between Section corners 40.00 chains north and south. Set post. Spruce 6"  
N77°W 15 links, Spruce 8" S75°E 23 links. 1968 - MDOT R/W map shows the 1/4 corner being 31.03'  
north of the survey C/L of Hwy. US-41, as measured along the Section line; the centerline forming an  
angle with the Section line of 80°42'11" in the SE quadrant, and a distance from corner G5 to the  
intersection of the centerline with the Section line of 2516.11'. Requesting more information  
pertaining to this corner, I was informed by MDOT U.P. survey unit personnel that no further  
information could be found regarding this corner's location, monumentation, or accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original post and accessories were not recovered. Found no acceptable evidence of the position  
of the original corner on the ground. Reestablished the position for the corner midway and on the  
Section line between Section corners 2594.72' north and south. The survey centerline of US41 was  
reconstructed from MDOT control and it was found to be 80.77' south (31.03' MDOT) of the  
reestablished corner position as measured along the Section line (which was found to make an angle  
with the centerline of 80°44'20"); distance from centerline to G5, a perpetuated original corner,  
2513.95' (2516.11' MDOT). From the reestablished position, stream crossings were found south 4.0  
chains (GLO 1.0 chains) and 14.5 chains (GLO 12.76 chains) and do not fit the record with respect to  
either the reestablished nor the MDOT positions, nor with the GLO distances to the Section corners  
north and south. I judged the scanty evidence on the 1968 R/W map to be insufficient to reestablish  
the position for the corner, it possibly indicating the recovery of a forester's approximate  
position, and did not rely upon it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
3" Tamarack N23°E 16.7' mrkd "1/4S NBT"  
4" Balsam S79°E 23.0' do  
7" Spruce S80°W 39.8' do  
3" Balsam N21°W 14.1' do  
Set sq'd cedar post adjacent.  
E= 7900049.841 N= 199554.467



Bearings are magnetic. Coordinates are MCS83 in meters (NAD83 (2011) Datum).  
Coord. Ref.=NGS PID RL1468: N= 199449.721 m. E= 7900600.011 m.

Signed by Stephan J. Szyszkoski Date 06/18/2014  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division