

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	K5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 14 T 48N R 32W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on K5 05/27/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K5) Corner common to Sections 11-12-13-14. 1970 - Corner remonumented by A.O.Enger RLS at a position recognized since at least 1935 or 1939. Set 1"IDx36" I.pipe with 4" alum. cap. Sugar Maple 11" N59E 39.9', Sugar Maple 15" S13E 18.0', Sugar Maple 12" S27W 24.1'.

(13-Sec. 14) Southeast 1/16 corner, Section 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) Found the 1970 monument in good condition but with broken cap, at record bearing and distance from the 1970 witnesses. The Sugar NE is in good condition with blazes overgrown, the Sugar SE is stump with measuring notch visible, the Sugar SW is a rotted stump. Accepted the monument as the best available evidence of the position of the original corner. Removed the broken cap and placed a new cap atop the pipe, appropriately stamped to identify the corner.

(13-Sec. 14) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K5) Fd. 1"ID I.pipe. Set 4" alum. MDNR cap atop. Set measuring nail with MDNR tag in the side of:
 13" Sugar N65E 40.85' 1970 NBT
 9" Sugar S11E 25.05' mrkd "S13 NBT"
 11" Sugar S79W 18.75' "S14 NBT"
 6" Sugar N33W 18.65' "S11 NBT"
 Sq'd cedar post adjacent. Bearings are magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Sugar N32E 30.3' mrkd "1/16S BT"
 8" Maple S68E 21.7' do
 4" Sugar S39W 25.1' do
 9" Maple N66W 20.5' do
 Sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/16/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16472
16473