

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____ _____ _____
2. Property Controlling in Section	S 27 T 48N R 33W S 27 T 48N R 33W S _____ T _____ R _____	1 5 _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 01/05/2011
5 05/16/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 27) West 1/16 corner between Sections 22 and 27. Not established in the original survey.

(5-Sec. 27) North 1/16 corner, Section 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 27) Established the corner midway and on the Section line between Section corner 1317.32'
west and Quarter corner 1317.32' east.

(5-Sec. 27) Established the corner midway and on a straight line between Quarter corner 1317.54'
north and Center of Section 27 1317.54' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
11" Cedar N37E 27.2' mrkd "1/16S BT"
7" Y.Birch S62E 3.45' do
6" Maple S64W 19.6' do
7" B.Spruce N10W 11.95' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(5) Set 5/8"x9" rebar cemented inside a 1"IDx11"
I.pipe with 4" alum. MDNR cap, all grouted into
a 3/4"dia.x1.5" deep hole drilled into bedrock.
Set measuring nail with MDNR tag in the side of:
4" Oak N07W 10.38'
4" Oak S57E 16.21'
7" Oak S29E 13.78'
4" Sugar N83W 17.47'
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/15/2011

For the Michigan Department of Natural Resources, Forest Management Division



16699

16700