

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 34W H13 T 47N R 34W H1 (same corner)	
2. Property Controlling in Section	S T R S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2		1	
3													
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 01/20/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H13) Quarter corner common to Section 34 T48N-R34W and Section 3 T47N-R34W. 1846 - Austin Burt, Deputy Surveyor, established the corner midway and on the Township line between Section corners 40.00 chains east and west. Spruce 7" N52E 11 links, Spruce 7" N46W 18 links. 1965 - Reestablished by F.J.Bray RLS midway and on line between Section corners. Set 1"ID Iron pipe with 4" aluminum cap. 14" W.Pine N41W 40.5 links, 7" Cedar S65E 49 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H13) The original post and accessories were not recovered. Found the 1965 monument in good condition and at record bearing and distance from the 1965 witnesses. The Cedar SE is standing dead. The W.Pine NW is in good condition. The monument was found to be 4.8' South and 1.6' East of the proportionate position intended to be monumented in 1965. I accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H13) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
16" W.Pine N34W 27.3' old marks (1965 NBT)
4" Cedar N72E 4.4' mrkd "1/4S NBT"
5" Cedar S58E 13.7' do
6" Tamarack S25W 14.1' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 06/24/2009
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995