

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 11 T 49N R 32W	14
	S 11 T 49N R 32W	15
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 14 06/07/2011 15 10/28/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 11) South 1/16 corner between Sections 11 and 12. 1942 - Norman T. Thompson RLS set Balsam post midway between Quarter corner and Section corner. BT Balsam 12" S33E 4.3'. Mr. Thompson reports the 1/2 mile to measure 2640 ft.

(15-Sec. 11) West 1/16 corner between Sections 11 and 14. Not established in the original survey. ca. 1942 - Norman T. Thompson RLS set Balsam post in road 1327' west of the 1/4 corner. New B.T. Maple 5" S17E 16.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 11) The 1942 monument and accessory were not recovered. Reestablished the corner midway and on the Section line between Section corner 1317.80' south and Quarter corner 1317.80' north.

(15-Sec. 11) Found no evidence of prior monumentation. Established the corner midway and on the Section line between Section corner 1325.71' west and Quarter corner 1325.71' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Sugar N15E 13.05' mrkd "1/16S BT"
5" Balsam S23W 3.75' do
5" Sugar S57W 17.2' do
8" Sugar N75W 20.7' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
14" Sugar N02W 51.3'
7" Sugar S78E 9.2'
12" Sugar S11E 37.45'
7" Sugar S87W 12.95'
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/27/2011

For the Michigan Department of Natural Resources, Forest Management Division

