

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 2 T 49N R 32W 14	_____
	S 12 T 49N R 32W 1/64 E. of K3	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 14 05/23/2011
64th 05/24/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 2) South 1/16 corner between Sections 1 and 2. Established in 1942 by Norman T. Thompson
RLS 20.00 chains north of Section corner. Set balsam post. BT Maple 4" East 18.0'.

(1/64 E. of K3) West-West 1/64 corner between Sections 1 and 12, being the NE corner of the W1/2 of
the NW1/4 of the NW1/4 of Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 2) Found a wooden post near the corner position but could not verify that the post is that
set by Mr. Thompson. The post is approx. NE 17' from the position subsequently monumented.
Established the corner midway and on the Section line between Section corner 1311.95' south and
Quarter corner 1311.95' north.

(1/64 E. of K3) Established the corner on the Section line between Section corner 649.39' west and
Quarter corner 1948.18' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
The monument leans slightly East but the top
center of the cap marks the corner position.
Set measuring nail with MDNR tag in the side of:
5" Maple N33E 20.3'
8" Maple S61E 31.55'
6" Cherry S20W 12.4'
14" Spruce N40W 15.4'
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(1/64) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
Set measuring nail with MDNR tag in the side of:
5" Sugar N15E 32.65' mrkd "1/64S BT"
6" Sugar S78E 20.45' do
4" Sugar S03W 4.6' do
4" Sugar S65W 9.55' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/27/2011

For the Michigan Department of Natural Resources, Forest Management Division

