

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 32W	G9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/01/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1852 - Established by Guy H. Carleton, Deputy Surveyor.
Set post. Cedar 12" N60°W 19 links, Cedar 10" S58°E 14 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) The original post was not recovered. Found a 1"ID iron pipe, pinched top, set firm, at record
bearing and distance from possible OBT Cedar N60W 19 links, now a rotted windthrown stump with no
markings visible. The pipe fits reasonably well with 1852 line calls west to "begin to ascend" (3.5
ch. R, 3.4 ch. M); "foot of hill" (7.5 ch. R, 8.0 ch. M); "stream 10 links" (20.60 chains R, 19.5
ch. M; and "enter swamp" (44.0 ch. R, 43 ch. M). A large, very old, windthrown cedar stub with
blaze and axe marks would, if stood upright, face the pipe. Adjacent is an old squared cedar post,
rotted off and laying on the ground. Three blazed and painted trees face the pipe, an old blazed
and painted line runs east from the pipe, and painted and ribboned lines run west and south.
Distance to E9 was found to be 1.83 chains short of the 1852 record, about the same proportion as
found from C9 to E9, which is 1.65 ch. short. I note that Deputy Carleton's measurements in his
township have been found by the undersigned to be erratic and have been previously described by the
examiner in 1854 as "loose, precipitate, and defective". I accept the pipe as the best available
evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Found 1"ID pinched pipe. Cut off the top and
installed a 4"dia. cast aluminum MDNR cap,
projecting about 14" a.g.
Set measuring nail with MDNR tag in the side of:
7" Maple N33°E 2.75' mrkd "S22 NBT"
9" Maple East 11.0' do
4" Y.Birch S08°W 7.9' "S28 NBT"
13" Oak N49°W 8.45' "S21 NBT"
Set sq'd cedar post adjacent.
E= 7900115.564 N= 205124.010



Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID RL0041: N= 210246.990 m. E= 7895426.989 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/04/2013

For the Michigan Department of Natural Resources, Forest Resources Division