

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 49N R 32W E13

T 48N R 32W E1

T R (Same Corner)

2. Property Controlling
in Section

S T R

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on 11/12/2008 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 32-33 T49N-R32W and Sections 4-5 T48N-R32W. 1846 - Established by Austin
Burt Deputy Surveyor midway and on the Township line between Section corners 80.00 chains east and
west. 1978 - Corner remonumented and recorded by K.L.Sackett RLS who restored corner position at a
found old rotted post in a pile of rocks the position of which "fits good with corners east and west
and swamp edge south". Set 1"IDx24" I.pipe with 4" aluminum MDNR cap. 9" Spruce N18E 15.0', 9"
Spruce S35E 19.7', 6" Spruce N42W 32.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original post and accessories were not recorded. Found the 1978 monument of record and did not
accept it as marking the position for the corner. According to measurements made this date, the 1978
position is situated N39W 99.3' from the position monumented by the undersigned, being midway and on
the Township line between Section corners 1 mile east and west, proportionate to the 1846 US survey.
Measurements from the monumented proportionate position conform very well to the original record in 4
directions: North 5294.8'M (5287.9'R), South 5173.5'M (5171.1'R), East 5276.1'M (5280.0'R), West
5276.1'M (5280.0'R). The position also checks well with GLO record hill calls at 30.0 and 32.0
chains south. My measurements to other corners on Section 32 which were monumented or coordinated by
Mr. Sackett show no evidence of measurement blunder on Sec. 32. But the 1978 position, does not, in
fact, fit "good with corners east and west", is probably a perpetuation of an approximate position
established by an unknown party, and is not accepted.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Sugar N36E 4.2' mrkd "S33 NBT"
17" Spruce S71E 31.25' "S4 NBT"
5" Balsam S34E 19.8' "S4 NBT"
11" Spruce S22W 42.8' "S5 NBT"
Set sq'd cedar post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 01/12/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995