

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S 18 T 50N R 33W _____ S 20 T 50N R 33W _____ S _____ T _____ R _____	B6 16
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6				17		16		15		14		13	
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on B6 07/25/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B6) Center of Section 18. Not established in the original survey.

(16-Sec. 20) East 1/16 corner between Sections 20 and 29. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(16-Sec. 20) Established the position for the corner midway and on the Section line between Quarter
corner 1306.67' west and Section corner 1306.67' east. The corner position falls in a dead Balsam
Fir.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


(B6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
made firm in a mound of rock.
Set measuring nail with MDNR tag in the side of:
4" Sugar N04E 4.0' mrkd "C1/4 BT"
7" Sugar S72E 8.7' do
6" Sugar S02W 14.3' do
12" Sugar N51W 17.1' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
driven into a dead Balsam stump and made firm
with a mound of rock.
Set measuring nail with MDNR tag in the side of:
8" Y.Birch N34E 10.9' mrkd "1/16S BT"
28" Hemlock N76E 39.6' do
18" Cedar S01W 16.45' do
19" Maple S66W 2.2' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/24/2011

For the Michigan Department of Natural Resources, Forest Management Division



16753

16740