

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 33W	E9
	T 50N R 33W	A7
2. Property Controlling in Section	T R	
	T R	
	T R	
3. Miscellaneous Property in Sec.	T R	
	T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on E9 05/19/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E9) Corner common to Sections 20-21-28-29. 1849 - Established by Wm.Burt Deputy Surveyor. Set  
Maple post. Cedar 6" N27E 49 links, Hemlock 16" S44W 45 links. Found no subsequent record.

(A7) Section corner common to Sections 18-19 T50N-R33W and Sections 13-24 T50N-R34W. 1846 -  
Established by Austin Burt Deputy Surveyor. Set Hemlock post. Hemlock 10" S88E 31 links, Sugar 12"  
N55W 12 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) The original post and accessories were not recovered. Found no acceptable evidence of the  
position of the original corner on the ground. Reestablished the position for the corner by double  
proportionate measurement to the original record between Section corner 5226.69' West (5267.46' GLO),  
Quarter corner 2645.62' North (2640.0' GLO), Quarter corner 2638.57' East (2659.14' GLO), and Quarter  
corner 2645.53' South (2640.0' GLO).

(A7) the original post and accessories were not recovered. Found no evidence of the position of the  
original corner on the ground. Reestablished the position for the corner on the Range line between  
Section corners 5248.83' north and south, proportionate to the original record measurements.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
16" Ash S89E 20.9' mrkd "S28 NBT"  
10" Sugar S37E 21.1' do  
18" Maple S57W 9.3' "S29 NBT"  
12" Maple N26W 9.5' "S20 NBT"  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

(A7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
8" Sugar N77E 12.3' mrkd "S18 NBT"  
8" Sugar S50E 30.0' "S19 NBT"  
11" Sugar S58W 11.8' "S24 NBT"  
18" Hemlock N09W 9.5' "S13 NBT"  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/24/2011

For the Michigan Department of Natural Resources, Forest Management Division

