

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 33W	E7
	T	
	T	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/20/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E7) Corner common to Sections 16-17-20-21. 1849 - Established by Wm. Burt Deputy Surveyor. Set
Cedar post. Spruce 10" N39W 17 links, Spruce 14" S45E 26 links. 1940 and 1947 - Notes of Norman T.
Thompson RLS do not describe this corner but state distances west to C7 = 5272', reestablished D7 =
2636', F7 = 2636', and G7 = 5263'. June 2011 - Mr. Jim Stiglich, long-time area resident of the
SE1/4 of the SE1/4 of Section 17 told me that he remembers seeing an iron pipe or pin in the north
shoulder of Golf Course Rd. within the last ten years, at the corner position, in line with a very
old fence to the north, now removed. Mr. Stiglich showed the location of the fence to me on the
ground, noting that it passed between two trees, the stumps of which still exist.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) The original post and accessories were not recovered and have been destroyed by road
construction. Found no monumentation at the corner position. Reestablished the northing of the
corner at the position pointed out to me by Mr. Stiglich and the easting at extension of the
obliterated old fenceline to the north. I note that this position falls in line with a forestry
painted line to the south and with a dead and down Birch with an old forestry location poster
attached. I found distances east and west to F7 and to reestablished D7 to be both 2632.57', in
proportion to N.T.Thompsons measurements from 1940 and 1947. The center of paved Golf Course Rd. is
10.5' south. I note that a position proportionate to the original record distances between corners
1/2 mile N,S,E, and W is only 4.3' north of the corner thus reestablished.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
buried in the N. shoulder of Golf Course Rd.
0.4' deep and 0.5' N. of the N. edge pavement.
Set measuring nail with MDNR tag in the side of:
6" twin Maple N18E 39.2' mrkd "S16 NBT"
6" Y.Birch S24E 51.9' "S21 NBT"
Power Pole #503316L26 S01E 32.05'
Power Pole #503316L25 N33W 12.9'
Set sq'd Cedar post 3' north.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/24/2011

For the Michigan Department of Natural Resources, Forest Management Division