

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 33W	D7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/20/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D7) Quarter corner common to Sections 17 and 20. 1849 - Established by Wm.Burt Deputy Surveyor
midway and on the Section line between Section corners 40.00 chains east and west. Set Cedar post.
Cedar 12" N31E 11 links, Cedar 14" S73W 17 links. 1947 - Notes of Norman T. Thompson RLS state: "Len
and Rus chained this mile. Found it to be 5272'. Set 1/4 cor. on porp. [sic] measurement, 2636'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D7) The original post and accessories have been destroyed by road construction. Found no evidence
of prior monumentation at the corner position. Recovered monumentation along the Section line 190.6'
east and also along the south R/W line of Golf Course Road at deeded parcel corners 355' and 420'
east of the corner position. By holding these monuments and extrapolating to recreate the 1/4 corner
position, I find that the position for D7 falls at an occupied field line to the south and that the
distance from D7 to F7 is 5265.14'. N.T.Thompson records 5272' between D7 and F7. At a distance
prorated to Thompson's measure east from D7, 2632.57', I find evidence of a north-south line,
confirmed by long-time resident of the SE1/4-SE1/4 Sec. 17, Mr. Jim Stiglich, to be the Sec. line
between 16-17 and 20-21. I accept this corroboration of found parcel monumentation, record
measurements, and old lines on the ground as confirmation of the recovery of the previous
reestablishment of the position of the corner. The monuments on the south R/W of the road are noted
in parcel deeds as being 58' south of the Section line. I therefore reestablish the corner
58' north of the monumented south R/W of Golf Course Road and 420.0' (record meas.) west of the NE
cor. of parcel owned by Scott Tupciauskas, the easterly line of this parcel being found monumented at
the south R/W with a 1" dia. hexagonal iron bar. From the corner the c/l of the gravel Golf Course
Road is 25' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Maple N02E 38.0' mrkd "1/4S NBT"
3" Maple N83E 46.0' do
14" Cedar S02W 49.0' do
4" Maple N35W 26.6' do
Set sq'd cedar post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/24/2011

For the Michigan Department of Natural Resources, Forest Management Division