

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 34W	G12
	T R	
	T R	
2. Property Controlling in Section	S 28 T 50N R 34W	14
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G12 06/20/12  
14 12/19/11 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 28) South 1/16 corner between Sections 27 and 28. Not previously monumented.

(G12) Quarter corner common to Sections 33 and 34. 1849 - Established by Wm. Burt Deputy Surveyor  
midway and on the Section line between Section corners 40.00 chains north and south. Set Hemlock  
post. Fir 5" N75E 5 links, Spruce 8" S73W 15 links. 1854 - Examiner A.B. Wood notes the BTs as  
found: Fir 5" N70E 5 links, Fir 6" blown down. Dep. Wood took additional BT: Hemlock 10" N87W 18  
links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 28) Established the position for the corner midway and on the Section line between Section  
corner 1317.19' south and Quarter corner 1317.19' north.

(G12) The original post and accessories were not recovered. The examiner's accessory was not  
recovered. Found no evidence of the position of the original corner on the ground. Reestablished  
the position for the corner midway and on the Section line between Section corners 2648.12' north and  
south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" B.Spruce N31E 6.9' mrkd "1/16S BT"  
5" B.Spruce N80E 2.45' do  
5" Hemlock S65W 8.25' do  
8" B.Spruce N33W 5.4' do  
Set sq'd cedar post adjacent.

(G12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
12" Y.Birch N19E 13.2' mrkd "1/4S NBT"  
5" Maple N39E 10.0' do  
5" Sugar S52E 13.6' do  
5" Sugar S71W 12.8' do  
Set sq'd Cedar post adjacent.

Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 12/12/2012

For the Michigan Department of Natural Resources, Forest Resources Division

