

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 34W	I8
	T R	(GCDB 500340)
	T R	
2. Property Controlling in Section	S 22 T 50N R 34W	14
	S T R	(GCDB 500320)
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 18 11/04/15 14 11/04/15 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I8) Quarter corner common to Sections 22 and 23. 1849 - Established by Wm. Burt, Deputy, midway
and on the Section line between Section corners 40.00 chains north and south. Set Hemlock post.
Sugar 10" N25°W 10 links, Y.Birch 15" S50°E 13 links. Found no subsequent record.

(14-Sec. 22) South 1/16 corner between Sections 22 and 23.
Not previously monumented.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I8) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner midway and on the Section
line between Section corners 2622.69' north and south.

(14-Sec. 22) Established the position for the corner midway and on the Section line between Section
corner 1311.34' south and Quarter corner 1311.35' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I8) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" Y.Birch N24°W 17.4' mrkd "1/4S NBT"
6" Sugar S28°E 16.15' do
8" Y.Birch S84°W 8.5' do
3" Y.Birch N60°W 7.9' do
Set sq'd cedar post adjacent.
E= 7882886.357 N= 215873.789

(14) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
12" Y.Birch N03°W 12.55' mrkd "1/16S BT"
6" Sugar N73°E 37.05' do
6" Sugar S41°E 34.8' do
11" Y.Birch S36°W 16.2' do
Set sq'd cedar post adjacent.
E= 7882876.213 N= 215474.265

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID D08499: N= 221257.621 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski Date 01/21/2016
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division