

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 31W C-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 573 - 574.

Hilda J. Kobillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T50N, R31W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

See back of form.

M.D.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


C-1; Closing Corner common to Sections 5 and 6, T50N, R31W.

Found a 1" x 36" iron pipe in agreement with both of Mr. Thompson's new bearing trees the condition of each as described in Part A. From this monument a moderately decayed hemlock stump approximately 30" in dia. bears west a distance of 55 feet. A 28 foot section of fallen trunk too far gone for marks bears N70°E from the stump. This monument accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R31W.

See back of form.



Signed by *Michael Mileski*

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T50N, R31W.

Originally established during U.S. Survey conducted by Guy Carleton, D.S. in 1852 and monumented with a wood post witnessed by a

Sugar Maple 14 S03°E 25 lks. (Gone)

and a

Sugar Maple 14 S76°E 47 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes possibly taken in 1943 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he reestablished the corner at record U.S. distance (55.44 feet) east from a recovered hemlock U.S. line tree. Mr. Thompson set a hemlock post and noted the following new bearing trees:

Sugar Maple 4 S88°E 10.8'
(Presently alive and 10" in dia. having a healed mid-trunk face blaze.
Set 60d spike S/side East 10.8')

and a

Hemlock 4 S68°W 12.2'
(Presently alive and 13" in dia. having a healed lower face blaze.
Set 60d spike N/side S66°W 12.20')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R31W.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	S/side	8" Sugar Maple	N65°E	26.58'
Set 60d spike	NE/side	10" Sugar Maple	S56°E	23.90'
Set 60d spike	NW/side	18" Sugar Maple	S36°W	28.61'
Set 60d spike	N/side	4" Sugar Maple	N65°W	20.95'

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".