

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

MAY 05 1997

For corners in

COMMISSION
Baraga
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---|------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | A-1* |
| | T <u> </u> R <u> </u> | |
| | T <u> </u> R <u> </u> | |
| | T <u> </u> R <u> </u> | |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | |
| | S <u> </u> T <u> </u> R <u> </u> | |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | |
| | S <u> </u> T <u> </u> R <u> </u> | |

4. Lot No. , Recorded Plat
5. Private Claims

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1; Northwest Corner Section 6, T51N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1; Northwest Corner Section 6, T51N, R33W;

Found and accepted a 1" x 23" iron rod sharpened to a point projecting 2" above ground as perpetuated by Robert Crampton, P.S.. The corner falls in the center of a north-south 10' wide unimproved road which is unused and overgrown at this point. (Continued on back of form.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1; Northwest Corner Section 6, T51N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location flush with the ground. Reset found iron rod with pointed end upward along the north side of the county monument.

- | | | | | | |
|------|--------------|---------|-----------------|-------|--------|
| i) | Set 7" spike | N/side | 13" Cedar | S79°E | 39.50' |
| ii) | Set 7" spike | SE/side | 6" Cedar | S51°W | 24.40' |
| iii) | Set 7" spike | S/side | 6" Cedar | West | 42.35' |
| iv) | Set 7" spike | NE/side | 6" Black Spruce | N46°W | 31.02' |
| | | | Location Post | East | 3.0' |

(i) and (ii) are Crampton new bearing trees and are further described in Part A.

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

* This corner is also A-13 of T52N, R33W, Baraga County.
This corner is also M-1 of T51N, R34W, Baraga County.
This corner is also M-13 of T52N, R34W, Houghton County.

RECEIVED FOR RECORD THIS 19TH DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 706-707.

Telda McAnty
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
10-30-96
Telda McAnty

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 18 Nov 1996
LIBER 4 PAGE 706



A. Description of original monument and accessories and/or subsequent restoration:

A-1; Northwest Corner Section 6, T51N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 20 S17°W 19 lks.

and a

Fir 10 N46°E 29 lks.

According to a Land Corner Recordation Certificate filed by Robert Crampton, P.S. #24591 and recorded 20 December 1984 in Liber 2 page 119, Houghton County Records, a "1 (in.) iron rod in the centerline of an old road bed and on a projection of two old fences East and West of the corner" was recovered and accepted. A Certificate of Survey prepared by Mr. Crampton dated 23 November 1984 indicates for the mile north of the township corner there is a deflection of 0°48'24" to the west at the ¼ corner with the south one-half mile measuring 2642.87 feet and the north one-half mile measuring 2642.56 feet. The Sturgeon River crosses the south one-half mile once and the north one-half mile twice. Mr. Crampton recovered a 1" square pin at the E¼ Cor. Sec. 36, T52N, R34W and a 1" hexagonal pin at the NE Cor. Sec. 36, T52N, R34W.

To the south of the township corner an iron rod was recovered and is most likely monumenting an original corner position. See LCRC, recorded 30 July 1996, Liber 4 page 623, Baraga County Records, filed by myself. The W¼ Cor. Sec. 6, T51N, R33W is considered lost. This mile measured 5322.77 feet (US=5306.40')

Mr. Crampton did not remonument the corner. He noted the following new bearing trees:

10" Cedar S78°E 39.5'
Presently alive and 13" in diameter having a nail and metal tag marked "RLS 24591" facing the monument. Set a 7" spike on the N/side.
Measured S79°E 39.50'

6" Cedar S50°W 24.4'
Presently alive and 6" in diameter having a nail and metal tag marked "RLS 24591" facing the monument. Set a 7" spike on the SE/side.
Measured S51°W 24.40'

12" Aspen S76°W 20.0'
Presently alive and 12" in diameter. Did not find Crampton nail and tag in tree.

6" Cedar N40°W 30.2'
Presently alive and 7" in diameter leaning heavily to the east and having a nail and metal tag marked "RLS 24591" facing the monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This road extends south along the range line in various stages of improvement to approximately ¼ mile south of the W¼ Cor. Sec. 18, T51N, R33W. To the north this road is unused and overgrown and extends an unknown distance. Six feet north of the corner an old partially down cedar post fence extends to the east. Replaced the found iron rod with a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap. Accepted as the best available evidence of the position of the original corner.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION