

# SURVEY & REMONUMENTATION

FEB 23 1998

## SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 52N R R33W

#8) North MC  
between A-3 and  
A-4

2. Property Controlling  
in Section

S      T      R     

3. Miscellaneous  
Property in Sec.

S      T      R     

4. Lot No.         , Recorded Plat         

5. Private Claims         

I, Michael Mileski, in a field survey on 5 December, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MC #8; North Meander Corner between A-3 and A-4, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by an

Elm 12 N35°W 25 lks.

According to a cruiser's report prepared by P.A. Larsen dated August/September 1905, the U.S. bearing tree was recovered. No monument was set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MC #8; North Meander Corner between A-3 and A-4, T52N, R33W;

This corner was considered lost and reestablished on line at the proportionate distance between the W¼ corner of section 7 and the NW corner of section 7. This corner position falls approximately 65 feet north of the right (north) bank of the Sturgeon River. Wesley Myllyla, an 86 year old, lifelong resident of the area stated that the Sturgeon River has drastically changed course during his lifetime. A witness corner was established on the section line at a distance of 37.00 feet southerly of the proportioned meander corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC #8; North Meander Corner between A-3 and A-4, T52N, R33W;

The witness corner described in Part B was monumented with a 1"(I.D.) x 36" galvanized iron pipe with cap stamped as to location flush with the ground.

Set 7" spike	SE/side	7" Box Elder	N43°E	30.93'
Set 7" spike	S/side	6" Elm	N74°E	18.86'
Set 7" spike	N/side	Power Pole	N83°W	30.37'
		6' Steel fence post w/ yellow sign	South	1.5'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

LIBER 4 PAGE 823

RECEIVED FOR RECORD THIS 31ST  
DAY OF DECEMBER A.D. 1997 AT  
10:30 A.M. AND RECORDED IN  
LIBER 4 OF LAND CORNER  
RECORDATION RECORDS ON PAGE  
823

*Relda Bishop*


BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

10-9-97



Signed by *Michael Mileski*  
Surveyor's Michigan License No. 39091

Date 23 Dec 1997