

FEB 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
BARRY
(county)

Located In:

Corner Code #

1. Public Land Survey
WEST 1/4 CORNER OF
SECTION 19
BALTIMORE TOWNSHIP
ON RANGE LINE

T 2N R 8W
T R
T R
T R

A-8



2746

Page: 1 of 1
12/17/1998 12:35P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling in Section S T R
S T R

3. Miscellaneous S T R

4. Lot No , Recorded Plat
5. Private Claims

I, Brian Reynolds, in a field survey on 13 JULY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
2. COUNTY SURVEYOR RECORDS: A.C. WILLSON, 26 JUNE, 1867 (L-1, P.167-169) "SOUTH FROM NW CORNER 39.98 TO W 1/4 POST" NO WITNESSES GIVEN
3. PRIVATE NOTES: UNRECORDED L.C.R.C. BY BRIAN REYNOLDS, P.S. #31602, 9 NOV, 1993; "COULD NOT LOCATE CORNER AS ESTABLISHED BY WILSON. PROJECTED LINE FROM E 1/4 CORNER THROUGH EXISTING CENTER OF SECTION AND INTERSECTED RANGE LINE NORTH OF E 1/4 POST OF SEC 24, HOPE TWP. SET STANDARD MONUMENT AND CAP AT THIS LOCATION. GLO JOG COMPUTES 11.88', MEASURED JOG = 12.37' " NAIL & TAG IN NORTH SIDE 12" POPLAR S32°W 25.82' NAIL & TAG IN WEST SIDE 14" BEECH S13°W 44.55' NAIL & TAG IN NORTH SIDE 20" OAK N84°E 36.09' NAIL & TAG IN SOUTHEAST SIDE 24OAK N49°E 32.27' E 1/4 POST SEC. 24 HOPE TWP. SOUTH 12.37' IN OLD N & S FENCE OLD FENCE TO EAST, SOUTH 18'+/-


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND MONUMENT AND ALL WITNESSES BY REYNOLDS AS MENTIONED IN #3 ABOVE. THAT POSITION AS DESCRIBED WAS PRESENTED TO THE PEER GROUP FOR REVIEW IN 1993. IT WAS DECLINED AT THAT TIME, THE PEER GROUP WANTING FURTHER TIES TO OCCUPATION LINES TO DETERMINE IF THE OCCUPATION FENCE EAST 18' SOUTH WAS CONSISTENT WITH 1/4 LINE OCCUPATION IN THE INTERIOR OF SECTION 19. THAT INFORMATION WAS PROVIDED IN 1998, AND THE CORNER APPROVED TO BE SET AT THE MEAN OF THE ADJACENT GOVERNMENT JOGS FROM PREVIOUSLY APPROVED M-8 T2N R9W. REMOVED FOUND MONUMENT AND RESET IT AT THE GOVERNMENT JOG (11.88').

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
FOUND NAIL & TAG IN THE NORTH SIDE 12" POPLAR S27°W 25.35'
FOUND NAIL & TAG IN THE WEST SIDE 14" BEECH S08°W 43.70'
FOUND NAIL & TAG IN THE NORTH SIDE 20" OAK N77°E 35.22'
FOUND NAIL & TAG IN THE SOUTHEAST SIDE 24OAK N42°E 32.68'
M-8, T2N, R9W, LIES SOUTH 11.88'
OLD FENCE TO EAST, SOUTH 18'+/-
IN OLD N & S FENCE

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
13 July 98
BRIAN REYNOLDS
BR
COUNTY SURVEYOR



Signed by Brian Reynolds
Surveyor's Michigan License No 31602

Date DEC 15, 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971
REVISED MAY 14, 1975 REVISED JANUARY, 1993 REVISED OCTOBER 1995