

COUNTY OF
REMONUMENTATION

MAY 20 1997

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED

DEC 9 2 09 PM '96

Sandy Schandelmayer

REGISTER OF DEEDS

002425

Register of Deeds Stamp & File Number

For corners in

BARRY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 3 R 7W

E-2

1/4 COR COMMON TO

SEC'S 4

CASTLETON TWP.

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

4. Lot No. , Recorded Plat

5. Private Claims

I, RAYMOND MOORED, in a field survey on MAY, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

COUNTY SURVEYOR RECORDS SET POST A.D. RORK JUNE 20, 1866 (L.2, P.105)

NOT SET BY GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

COULDN'T LOCATE CORNER BY RORK. SET STANDARD BARRY COUNTY REMON IRON W/CAP AT INTERSECTION OF 1/4 LINES.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BARRY COUNTY REMON IRON W/CAP

-NE CORNER HOUSE S45DEG. W 107.24'

-NAIL & TAG IN N SIDE 10" CHERRY S55DEG W 47.92'

-NAIL & TAG IN N SIDE 12" CHERRY S80DEG. E 17.88'


-NAIL & TAG IN S SIDE 10" ELM N40DEG.E 21.65'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 NOV. '95

BRIAN REYNOLDS

COUNTY SURVEYOR



Signed by

Raymond Moored

Surveyor's Michigan License No.

26463

Date

12/2/96