

APR 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 2 PAGE 60  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BENZIE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 27NR 13W

A-6

T R

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Sec.

S

T R

S

T R

STATE OF MICHIGAN  
BENZIE COUNTY  
RECORDED

15 Jan 1998 4:04:24 PM

MICHELLE R. GRAY  
REGISTER OF DEEDS  
# PAGES one

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, CARL KIISKILA, in a field survey on OCTOBER 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6

G.L.O. SET POST - 14" HEMLOCK N46°W 18.5' AND 14" BEECH S42°E 46.2'. HAROLD R. BRUNING SET BENZIE CO. MARKER MIDWAY AND ON LINE BETWEEN NW CORNER AND SW CORNER OF SEC 18. DNR SURVEY CREW FOUND BENZIE CO. MARKER MAY 20, 1993 FITTING HAROLD R. BRUNING WITNESSES AND MAY 23, 1974 L.C.R.C. LIBER 1, PAGE 121.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6

FOUND BENZIE CO. MARKER PER HAROLD R. BRUNING L.C.R.C. LIBER 1, PAGE 121 AND WITNESSES.

Attested by Peer Group

In accordance with P.A. 345

Chairman Carl T. Kiiskila


Date 12/7/1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6

FD 1974 BENZIE CO MON, SET CARSONITE POST.  
19" BEECH N45°W 7.18' (DROVE NAIL W/TAG SW SIDE).  
15" BEECH N46°E 11.37' (FD NAIL W/TAG NW'LY SIDE)  
18" S. MAPLE N80°E 17.74' (FD NAIL W/TAG S. SIDE)  
17" S. MAPLE S05°E 15.30' (FD NAIL W/TAG E. SIDE)  
ATV TRAIL (NW - SE) IS 25' SOUTH.

\* = PS H. BRUNING 1974 WIT.



Signed by Carl T. Kiiskila

Date 4-9-97

Surveyor's Michigan License No. 33981