

**FEB 23 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T47N R2E	D-5
	T R	
	T R	
	T R	
2. Property Controlling	S T R	
in Section	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

I, Larry R. Rogers, P.S., in a field survey on December 01, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(D-5) 1/4 Corner common to Sections 8 and 17, Township 47 North, Range 2 East.

The original corner post was placed in 1845 by John Mullett. In 1908, Frederick Brown found the original corner post in place and recorded a distance of 2609 feet to the Northeast corner of Section 17. 1919 County Surveyor notes also recite a distance of 2615 feet to the Northeast corner of Section 17, but Brown noted that he felt 2609 feet was the correct distance. In 1993, W.L. Karr P.S. 27450 recovered the rotted base of a 4" wood post he felt 6" below ground surface. Post falls on the extension of fence to North, East and South. Karr set a 1/2" iron pin with P.S. cap number 27450 in center of wood post, established 5 new witnesses and filed a L.C.R.C. in Liber 8 at Page 249 of the Chippewa County Corner Records.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(D-5) 1/4 Corner common to Sections 8 and 17, Township 47 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Recovered 1/2" capped iron pin as set by Karr and three witnesses. Distance to Northeast corner of Section 17 measures 2604.7 feet (CS = 2609). Accepted corner position as found and established one new witness.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(D-5) 1/4 Corner common to Sections 8 and 17, Township 47 North, Range 2 East.


Corner is a 1/2" iron pin with P.S. cap number 27450 on the extension of fences to North and East.

**Witnesses:**

12" Spruce	S51°W	40.59 feet
6" Maple	N65°W	21.24 feet
7" Spruce	S40°E	52.64 feet
5" Cedar (in clump)	N76°E	36.78 feet
Corner Fence Post	North	9.65 feet

Bearings are magnetic compass bearings. All distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by



Larry R. Rogers, P.S.

Surveyor's Michigan License No. 29251

Date

29 DEC 2000

\$7.00 LAND CORNER

\$2.00 MSSR

9 FEB 2001 10:32:06 AM Receipt #1201

RECEIVED FOR RECORD

CHIPPewa COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 11 PAGE 228

Register of Deeds Stamp & File Number

