

SURVEY & REMONUMENTATION

FEB 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 Chippewa County Remonumentation Corner

For corners in

Chippewa County

Located in:

Corner Code #

1. Public Land Survey

T47N R2E

E-3

2. Property Controlling
in Section

S

T



3. Miscellaneous
Property in Sec.

S

T

4. Lot No.

, Recorded Plat

5. Private Claims

47.00 LAND CORNER

42.00 MSSR


9 FEB 2001 10:32:54 AM Receipt #1201
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 11 PAGE 231

Register of Deeds Stamp & File Number

I, Larry R. Rogers, P.S., in a field survey on December 08, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

(E-3) Section Corner Common to Section 4, 5, 8 and 9, Township 47 North, Range 2 East.

The original corner post was placed in 1845 by John Mullett. Corner was re-established prior to 1901 by County Surveyor Stillwell. 1901 and 1919 County Surveyor notes refer to "Stillwell" corner and recite a distance of 5187/5188 along the South line of Section 5.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-3) Section Corner Common to Section 4, 5, 8 and 9, Township 47 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner or Stillwell corner. Corner position was re-established by double proportionate between the South 1/4 corner of Section 5, the Southeast corner of Section 3, the East 1/4 corner of Section 5 and the East 1/4 corner of Section 8. Distances North and South to 1/4 corners measure 2635.75 feet (GLO = 2640). Distance West to South 1/4 corner of Section 5 measures 2595.1 feet (CS = 2594). Distance to Southeast corner of Section 3 measures 10586.68 feet (GLO = 10581.12 feet)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-3) Section Corner Common to Section 4, 5, 8 and 9, Township 47 North, Range 2 East.

Corner is a 3/4" x 48" rebar with plastic Chippewa County Remonumentation Cap in 6" of standing water.

Witnesses:

3" Ash Post	North	1.0 foot
14" Red Maple	N34°E	44.21 feet
6" Red Maple	N80°W	23.96 feet
6" Red Maple	S29°W	31.50 feet
8" Red Maple	S86°E	30.24 feet

Bearings are magnetic compass bearings. All distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by

Larry R. Rogers, P.S.

Surveyor's Michigan License No. 29251

Date

29 DEC 2000