

FEB 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner \$7.00 LAND CORNER

For corners in

Chippewa County

Located in:

Corner Code #

- | | | | |
|-------------------------|---|----------|---------------|
| 1. Public Land Survey | | T47N R2E | G-3 |
| | | T R | |
| | | T R | |
| | | T R | |
| 2. Property Controlling | S | T R | |
| In Section | S | T R | |
| 3. Miscellaneous | S | T R | |
| Property in Sec. | S | T R | |
| 4. Lot No. | | | Recorded Plat |
| 5. Private Claims | | | |

\$2.00 MSSR

9 FEB 2001 10:47:27 AM Receipt #1201

RECEIVED FOR RECORD


CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 11 PAGE 241

Register of Deeds Stamp & File Number

I, Larry R. Rogers, P.S., in a field survey on December 07, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

(G-3) Section Corner common to Sections 3, 4, 9 and 10, Township 47 North, Range 2 East.

The original corner post was placed in 1845 by John Mullett. County Surveyor Fred Brown "saw cross lines in 1924 and put in post". Same notes refer to North - South road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-3) Section Corner common to Sections 3, 4, 9 and 10, Township 47 North, Range 2 East.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner position, any subsequent restoration, or North - South road. Re-established corner position by double proportionate measurement between the Southwest corner of Section 4, the Southeast corner of Section 3, the Northwest corner of Section 3 and the East 1/4 corner of Section 9. The distance to the Southwest corner of Section 4 is 5289.38 feet (GLO= 5286.6 feet); to the Southeast corner of Section 3 is 5297.3 feet (GLO = 5294.52 feet); to the Northwest corner of Section 3 is 5108.82 feet (GLO = 5280 feet); and to the East 1/4 corner of Section 9 is 2554.41 feet (GLO = 2640 feet).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-3) Section Corner common to Sections 3, 4, 9 and 10, Township 47 North, Range 2 East.

Corner is a 3/4" x 24" rebar with stamped aluminum remonumentation cap set at the Northwest base of a 12" Sugar Maple.


Witnesses:

10" Yellow Birch	N36°W	50.81 feet
8" Sugar Maple	N26°E	26.34 feet
12" Sugar Maple	N81°E	18.33 feet
8" Yellow Birch	S34°W	56.29 feet

Corner falls on East - West brush line.

Bearings are magnetic compass bearings. All distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by


Larry R. Rogers, P.S.

Date

29 DEC 2000

Surveyor's Michigan License No. 29251

