

# SURVEY & REMONUMENTATION

SEP 18 1997

COMMISSION

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On July 23, 1997

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

*Robert Schumeling*  
Chairman

For corners in

DELTA

(County)

Located In:

Corner Code ##

1. Public Land Survey
 

T	41 N	R	23 W		
				MC C-3/4 LT BANK	(23)
T	41 N	R	23 W	MC C-3/4 RT BANK	
T		R			
T		R			
2. Property Controlling in Section
 

S	T	R		
S	T	R		
3. Miscellaneous Property in Sec.
 

S	T	R		
S	T	R		

28 July 1997

9:00 o'clock a.m.

8 Page 224

*Walter C. Thoren*  
Delta County, Ill. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_  
C-3/4 MC ON LT BANK ESC RIV C-3/4 MC ON RT BANK ESC RIV

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on 07 MAY, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-3/4 [MC LT BANK]- A.MERRYWEATHER, D.S. - 1847-WOOD POST (BIRCH 4"N80"E-20 LINKS)  
NO RECORD EVIDENCE OF CORNER RECOVERY AND/OR SUBSEQUENT CORNER RESTORATION

C-3/4 [MC RT BANK]- A.MERRYWEATHER, D.S. - 1847 -WOOD POST (CEDAR 06"-CORNER TREE)  
NO RECORD EVIDENCE OF CORNER RECOVERY AND/OR SUBSEQUENT MONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3/4 [REF MON TO MC ON LT BANK] NO CORNER EVIDENCE FOUND. ESTABLISHED REFERENCE MONUMENT AT EDGE OF UPLAND VEGETATION & ON SECTION LINE BETWEEN SECTIONS 7/8.

C-3/4 [REF MON TO MC ON RT BANK] NO CORNER EVIDENCE FOUND. ESTABLISHED REFERENCE MONUMENT AT EDGE OF UPLAND VEGETATION & ON SECTION LINE BETWEEN SECTIONS 7/8.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3/4 [LT BANK] SET 5/8"x18" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.

CEDAR 13"	CEDAR 6"	CEDAR 5"	LEFT BANK ESCANABA RIVER
N25°W	N35°E	S40°E	SOUTH
29.12'	18.76'	15.87'	50'

C-3/4 [RT BANK] SET 5/8"x18" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.

CEDAR 9"	CEDAR 18"	RED PINE 9"	W.BIRCH 7"	RIGHT BANK ESCANABA RIVER
N10°W	S67°E	S15°E	S34°W	NORTH
5.51'	4.75'	35.69'	28.47'	23'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 7/23/97

Surveyor's Michigan License No. 16926