

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Delta
(County)

Located In:

Corner Code #/

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------------|
| 1. Public Land Survey | T | <u>42N</u> | R | <u>22W</u> | <u>E-5, C-4.</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 5/19/88, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-5. SE section corner of Section 8. Wood post, 1852. Sugar 8, S17W, 27 lks. Fir 10, N71E, 37 lks.
 C-4. West 1/4 corner of Section 8. Wood post. 1852. Cedar 12, S40E, 14 lks. Cedar 14, N15W, 25 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-5. Set by double proportion using the section corner 2 miles north and 1/4 corners 1/2 mile south, 1/2 mile west and 2 1/2 miles east. Corner falls in line with the E of a county road south. No E-W occupation lines evident.
 C-4. Set MPOL between the NW and SW section corners of Section 8. Cedar remains in the area but could not identify OBT's. Original survey record call for "Enter wetland course NW" at 50 lks. south of 1/4 corner. fits this location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---------------------------------|--------------------------|
| E-5. DNR Monument (Buried) | C-4. DNR Monument |
| 9" maple, N78E, 36.1' | 7" r.maple, S78W, 8.0' |
| 5" maple (in clump) S68E, 35.0' | 8" r.maple, N35W, 18.5' |
| 8" spruce, S72W, 44.0' | 12" r.maple, N36E, 25.0' |
| 8" maple, N83W, 40.6' | 9" r.maple, S73E, 22.7' |

Signed by David B. Babbitt Date 9-29-88
 Surveyor's Michigan License No. 21558