

Common to:
K-13 (M-13) T40-29
(K-13) (M-13) A13 41-28

M-13/A-13 T41N-R28W

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DICKINSON
(County)
NORWAY TOWNSHIP

Located In:

Corner Code #

1. Public Land Survey

T 41 N R 29 W

K-13

T 41 N R 29 W

M-13

T R

T R

T R

T R

T R

T R

2. Property Controlling
In Section

3. Miscellaneous
Property in Sec.

SURVEY &
REMONUMENTATION

MAR 24 2000

4. Lot No. , Recorded Plat

5. Private Claims

SECTION

I, JAMES H. MOORE, in a field survey on SEPTEMBER 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RECORDED
1999 NOV 30 PM 3:31

REGISTER OF DEEDS
DICKINSON COUNTY
RON MOORE, CLERK

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9			10			12
5													
6	18			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33			34			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13 CORNER COMMON TO SECTIONS 35-36, T41N-R29W
CEDAR POST BY AUSTIN BURT, D.S. 1846
PINE 14" N 50° E 16 LINKS
CEDAR 7" N 20° W 27 LINKS

M-13 CORNER COMMON TO SECTIONS 31-36, T41N-R28 & 29 W
CEDAR POST BY AUSTIN BURT, D.S. 1846
WHITE PINE 40" N 72° E 48 LINKS
CEDAR 14" N 25° W 17 LINKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 FOUND 1" PIPE WITH 4" MICHIGAN DEPARTMENT
OF CONSERVATION BRASS CAP, SET BY DEAN
DE LA MATER R.L.S. #13030.

M-13 FOUND 1" PIPE WITH 4" MICHIGAN DEPARTMENT OF
CONSERVATION BRASS CAP, SET BY BILL BUCKLER
R.L.S. #08887

1951 BEARING TREES

10" CEDAR N 60° W

28 LINKS

8" RED OAK S 49° W

46 LINKS

1956 BEARING TREES

9" ASPEN N 58° W

9 LINKS

7" BALSAM N 74° E

26 LINKS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 FOUND ABOVE DESCRIBED MONUMENT IN PLACE
NEW WITNESSES

M-13 FOUND ABOVE DESCRIBED MONUMENT IN PLACE
NEW WITNESSES

8" MAPLE N 63° E (M.B.) 17.10'

NAIL/TAG

6" MAPLE S 37° E (M.B.) 11.12'

NAIL/TAG

FOUND 16" RED OAK S 51° W (M.B.) 30.48'

NAIL/TAG

8" MAPLE N 69° W (M.B.) 43.65'

NAIL/TAG

CARSONITE MARKER SOUTH 0.80'

5" ASPEN

N 20° E (M.B.) 16.64'

NAIL/TAG

5" ASPEN

S 86° E (M.B.) 7.20'

NAIL/TAG

4" ASPEN

S 25° W (M.B.) 12.18'

NAIL/TAG

5" ASPEN

S 77° W (M.B.) 28.78'

NAIL/TAG

14" CEDAR


N 59° W (M.B.) 56.39'

NAIL/TAG

CARSONITE MARKER N 15° W

0.70'

Signed by



Surveyor's Michigan License No. P.S. 28423

Date

11-8-99

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON

11-23-99

COUNTY REPRESENTATIVE

LIBER 3 PAGE 9