

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 40N R 29W

G8

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Nov 02 2000

I, Paul R. Bressette

, in a field survey on , 20 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G8) Quarter corner common to Sections 21 and 22. 1849: James H. Mullett, DS. Set wood post witnessed by: Hemlock 8 N40E 16 lks.; Hemlock 8 S50W 22 lks. 2000: Found 1" iron pipe, not of record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G8) No evidence of original survey found. Measured north from found iron pipe 15 feet to definite edge of swamp (GLO-1 chain-66 feet); measured south 66 feet and fell on slope of hill (GLO-1 chain-66 feet calls for summit of hill); measured south 132 feet and fell on top of hill (GLO-2 chains-132 feet calls for leave swamp and ascend). Based on these measurements, found iron pipe was rejected. Mid-point and on-line position falls on edge of swamp, this position was also rejected. Using a proportion of 39 chains for south half mile and 41 chains for the north half mile results in a better overall fit to the terrain calls. Measured north 68 feet to edge of swamp (GLO-1 chain-66 feet), measured south 78 feet to center of ridge (GLO-1 chain-66 feet), measured south 160 feet to bottom of hill (GLO-2 chains-132 feet), this call not as definite as the two closer to the corner. Based on these measurements, corner position was reestablished by single proportion using 39 chains for the south half mile and 41 chains for the north half mile between the Northeast and Southeast corners of Section 21, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G8) DNR Monument

06" Cedar N62E 12.35' (1/4S,NBT)

05" Cedar S38E 24.7' (1/4S,NBT)

10" Cedar S40W 51.45' (1/4S,NBT)

09" Cedar N40W 16.25' (1/4S,NBT)

All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette

Date

Surveyor's Michigan License No. 37270

For the Michigan Department of Natural Resources - Forest Management Division