

SURVEY &  
REMONUMENTATION

DEC 18 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey T 41N R 27W C-4  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECORDS  
NOV 21 11:27  
DICKINSON COUNTY

Register of Deeds Stamp & File Number

I, Robert F. Perkins, in a field survey on Mar. 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4 East  $\frac{1}{2}$  Corner, Section 7  
Post John Burt, D.S. 1850  
Original Bearing Trees  
Y. Birch 18" N55°W 15 Lks.  
Cedar 10" S18°E 22 Lks.

ACCEPTED BY THE DICKINSON COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT  
345 OF 1990 AT A MEETING HELD ON

11-20-95

RAF


COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 No Evidence of Original Corner or Accessories Found.  
Found Iron Pin in South Shoulder of Gravel Road.  
Location agrees with Old Dickinson County Road Commission Records.  
Distances check to Section Corners North and South.  
Accepted Pin as Best Available Evidence of Corner Location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 Replaced Pin with 2 $\frac{1}{2}$ " Stamped Dickinson County Survey Monument  
buried 6" in Shoulder of Road.  
New Bearing Trees  
Cedar 7" S81°E (M.B.) 20.65'  
Cedar 8" N18°E (M.B.) 57.95'  
Spruce 6" N18°W (M.B.) 39.21'  
Spruce 5" N52°W (M.B.) 35.73'  
E Gravel Road  $\pm$ 12' N.E.



Signed by

Robert F. Perkins

Date

Nov. 7, 1995

Surveyor's Michigan License No.

12027

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983