

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
Felch Township		
1. Public Land Survey	T 42N R 29W	J03
	T 42N R 29W	H05
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jeremy J. Pipp, in a field survey on 8/01/2012AD do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J03) Quarter corner common to Sections 2 and 11. 1849: John Burt, DS. Lynn 24 Quarter  
Section Corner.

(H05) Quarter corner common to Sections 10 and 15. 1849: John Burt, DS. Set Sugar post  
witnessed by Sugar 8 S31E 26 links (17.16'), Sugar 14 N46W 30 links (19.80').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J03) No evidence of original survey or subsequent restoration found. Corner position  
reestablished by single proportionate measurement between the Southwest corner and the  
Southeast corner of Section 2. Position is accepted as a careful and faithful  
REESTABLISHMENT of the position of the original corner.

(H05) No evidence of original survey or subsequent restoration found. Corner position  
reestablished by single proportionate measurement between the Southwest corner and the  
Southeast corner of Section 10. Position is accepted as a careful and faithful  
REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J03) DNR monument  
10" Maple N07E 10.05' (1/4S,NBT)  
9" Maple S61E 20.17' (1/4S,NBT)  
11" Maple S50W 23.80' (1/4S,NBT)  
12" Maple N77W 25.32' (1/4S,NBT)  
All trees are blazed, scribed, painted,  
and signed. Measurements are to nail in  
side of tree, bearings are magnetic. A  
carsonite rail was set North 1.5 feet.

(H05) DNR monument  
17" Maple N14E 35.00' (1/4S,NBT)  
8" Maple S22E 37.57' (1/4S,NBT)  
9" Maple S29W 37.80' (1/4S,NBT)  
6" Maple N23W 33.35' (1/4S,NBT)  
All trees are blazed, scribed, painted,  
and signed. Measurements are to nail in  
side of tree, bearings are magnetic. A  
carsonite rail was set North 1.5 feet.

Signed by Jeremy J. Pipp  
Surveyor's Michigan License No. 50447

Date August 28, 2012

For the Michigan Department of Natural Resources, Office of Professional Surveyors and Facilities



20105

20106

Revised May 14, 1975  
Revised Jan., 1983  
Revised Oct., 1995