

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson (County) Located In: Corner Code #
1. Public Land Survey T 43N R 29W L03
2. Property Controlling in Section S 11 T 43N R 29W 1
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M). Contains numbers 1-36 and some symbols.

I, Jeremy J. Pipp, in a field survey on 6/28/2012AD 7/09/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L03) Quarter Corner common to Sections 1 and 12. 1848: Harvey Mellen, DS. Set Cedar post witnessed by: Spruce 12 N36W 25 links (16.50'); Cedar 14 S62E 8 links (5.28').

(01) West One-Sixteenth corner common to Sections 2 and 11. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L03) No evidence of original survey or subsequent restoration found. Several mounds of tree remains in area, but nothing definitive recovered. Corner position reestablished by single proportionate measurement between the Northwest corner and the Northeast corner of Section 12 and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

(01) Corner position established mid-point and on-line between the North One-Quarter corner and the Northwest corner of Section 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L03) DNR monument
5" Maple N35E 32.80' (1/4S,NBT)
4" Spruce S33E 17.21' (1/4S,NBT)
4" White Birch S13W 20.01' (1/4S,NBT)
8" Balmagilead N50W 20.85' (1/4S,NBT)
All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A carsonite rail was set North 1.5 feet.
(01) DNR monument
5" Cherry N27E 25.99' (1/16S,BT)
6" Ironwood S66E 11.96' (1/16S,BT)
11" Maple S57W 18.57' (1/16S,BT)
7" Maple N74W 28.38' (1/16S,BT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by [Signature] Date July 18, 2012
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources

