

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
FELCH TOWNSHIP		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 28 T 43N R 29W	11
	S 28 T 43N R 29W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Jeremy J. Pipp, in a field survey on 2/26/2013AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(11) Southwest One-Sixteenth corner of Section 28. Not set in original survey, no evidence of subsequent establishment.

(12) Center-South One-Sixteenth corner of Section 28. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11) Corner position established at the intersection of the South and West One-Sixteenth lines of Section 28.

(12) Corner position established mid-point and on-line between the Center One-Quarter corner and the South One-Quarter corner of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) DNR monument
4" Maple N56E 18.31' (1/16S,BT)
7" Maple S67E 23.13' (1/16S,BT)
8" Maple S32W 18.51' (1/16S,BT)
11" Maple N64W 14.67' (1/16S,BT)


All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(12) DNR monument
5" Spruce N79E 49.55' (1/16S,BT)
12" Maple S07E 44.91' (1/16S,BT)
8" Maple S80W 30.65' (1/16S,BT)
5" Aspen N22W 21.99' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy Pipp
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources



Date July 22, 2013

20187

20186