

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T___ R___
T___ R___
T___ R___
T___ R___

2. Property Controlling
in Section

S 2 T 44N R 27W 13
S 2 T 44N R 27W 16

3. Miscellaneous
Property in Sec.

S___ T___ R___
S___ T___ R___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

16 Oct 29 2001

13 Oct 18 2001

I, Paul R. Bressette, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (13) Southeast One-sixteenth corner of Section 2. Not set in original survey, no evidence of subsequent establishment.
(16) East One-sixteenth common to Sections 2 and 11. Found 1 1/2" iron pipe +/- 60 feet east of monumented position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (13) Corner position established at the intersection of the south and east one-sixteenth lines of Section 2.
(16) Found iron pipe rejected due to excessive distance from proper position. Iron pipe was set by forester for a timber sale.
Corner position established mid-point and on-line between the South Quarter corner and Southeast Section corner of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (13) DNR monument
7" Spruce S74E 21.75' (1/16S,BT)
5" Spruce S40W 28.6' (1/16S,BT)
7" Spruce N66W 21.8' (1/16S,BT)
8" Tamarack N08W 27.35' (1/16S,BT)
All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.
- (16) DNR monument
12" Spruce S83E 29.75' (1/16S,BT)
07" Spruce S22E 35.0' (1/16S,BT)
05" Spruce S37W 43.85' (1/16S,BT)
10" Maple N65W 60.0' (1/16S,BT)
All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division