

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Dickinson	Located In:	Corner Code #
(County)		
WELCH TOWNSHIP		
1. Public Land Survey	T 44N R 29W	F03
	T R	
	T R	
2. Property Controlling Section	S T R	
	S 4 T 44N R 29W	11
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

11/08/2012AD
Jeremy J. Pipp, in a field survey on 11/08/2012AD do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F03) Quarter corner common to Sections 4 and 9. 1848: John Burt,DS. Set Cedar Post
witnessed by Y. Birch 10 N05W 15 links (9.90'), Y. Birch 8 S25E 33 links (21.78'). 1976:
Michigan DNR (Arthur Enger PS#13581) Re-established proportionally on line between Sec.
Corners 39.889 chains West and 39.879 chains East. Placed a DNR monument witnessed by 6"
Cedar N70W 21.8' "1/4 S, NBT", 10" Cedar N77E 22.7' "1/4 S, NBT".

(11) Southwest One-Sixteenth corner of Section 4. Not set in original survey, no evidence
of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F03) Accepted found MDNR Monument and Two existing Witnesses. Left MDNR monument in place
and rewitnessed. Accepted found MDNR Monument and Witness remains as a careful and
faithful REESTABLISHMENT of the position of the original corner.

(11) Corner position established at the intersection of the South and West One-Sixteenth
lines of Section 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F03)	DNR monument	(11)	DNR monument
14" Spruce	N02E 18.06' (1/4S,NBT)	9" Spruce	NE 0.1' (1/16S,BT)
EX 11" Cedar	S81E 23.03' (1/4S,NBT)	7" Spruce	S70E 6.53' (1/16S,BT)
30" W. Pine	S44W 60.40' (1/4S,NBT)	11" Spruce	S21E 7.65' (1/16S,BT)
EX 11" Cedar	N64W 22.19' (1/4S,NBT)	7" Spruce	S88W 21.00' (1/16S,BT)

All trees are blazed, scribed, painted,
and signed. Measurements are to nail in
side of tree, bearings are magnetic. A
carsonite rail was set North 1.5 feet.

All trees are blazed, scribed, and
painted. Measurements are to nail in
side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp Date July 18, 2013
Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources, Forest Resources Division

20138

20139

