

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Gogebic
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 43N R 38W

Cr. 2-3

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Other #2

Register's Office }
Gogebic County } ss.

Received for record the
4th day of JANUARY
A. D. 19 92 at 1:40 o'clock

P m., and recorded in
Liber 4 of CORNERS

page 187
Richard J. Brown
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

PEER GROUP

Approved

5. Private Claims

Richard L. Doolin 1/20/94

I, Gary L. Pisoni, in a field survey on October 29, 19 92,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Zelotes B. Searls on July 30, 1851.

Original corner: Wood post

Original bearing trees:

Fir	10"	N 67°W	21 links (13.86 feet)
Fir	8"	N 44°E	21 links (13.86 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. Meander corner restored on the North bank of Lac Vieux Desert from an extension of the NW Section corner of Section 5 through the West quarter corner of Section 5 to the shore of Lac Vieux Desert.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read; T43N, R38W; S-6; S-5; M.C.; 1992; R.L.S. 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Balsam	8"	S 42°W	1.94 feet
Red Maple	15"	N 46°W	19.25 feet
Red Maple	15"	N 26°E	25.67 feet
Steel Sign Post		S 83°E	0.91 feet

Signed by Gary L. Pisoni

Date Nov. 20th 1992

Surveyor's Michigan License No. 27457



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983