

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in

Gogebic
(County)

Located In:

Corner Code ##

1. Public Land Survey T 44N R 41W C-1,2
T R 001
T R 001
T R 001
2. Property Controlling S T R
in Section S T R R & N
3. Miscellaneous S T R
Property in Sec. S T R 10/10/98

Received for record the
18TH day of APRIL
A. D. 1994 at 1:20 o'clock
P. M., and recorded in
Liber 5 of CORNERS
on page 25
Betty Lavin Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat PEER GROUP Approved
5. Private Claims _____

Richard L. Pisoni 4/7/94

I, Gary L. Pisoni, in a field survey on December 17, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by Algernon Merryweather, U.S. Deputy Surveyor on July 11, 1852.
Original Corner: 8" cedar corner tree
Original bearing tree:
Cedar 6" S 30°E 6 links (3.96 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found. I restored the meander corner position on the South shore of Big Mosquito Lake on line between the NW Section corner of Section 5 and the West quarter corner of Section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


At the corner position, I set a 3/4" outside diameter by 4 feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: T44N, R41W, M.C., S-6, S-5, 1991, RLS- 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Cedar (Existing)	11"	S 12°E	13.55 feet
Red Maple	5"	S 50°W	21.04 feet
White Spruce	6"	N 27°W	11.64 feet
Steel Sign Post		N 70°E	1.16 feet

Signed by Gary L. Pisoni

Date 3-23-94

Surveyor's Michigan License No. 27457



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983