

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Gogebic County

Register's Office }
Gogebic County } ss.

FOR CORNERS OF--:

LOCATED IN--:

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY T. 46 N. R. 42 W.

D-1

2. PROPERTY CONTROLLING IN SECTION T. N. S. R. E. W.

3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.

4. LOT NO. , RECORDED PLAT

5. PRIVATE CLAIMS

Quarter Corner

5 & 32

T. 46-47 N., R. 42W.

PEER GROUP

Approved

Received for record the
4TH day of January

A. D. 1992 at 2:00 o'clock

P m., and recorded in

Liber 4 of CORNERS

on page 196

Richard L. Drahn

Register of Deeds

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 4 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, U.S. Deputy Surveyor, in 1847.

Original bearing trees:

Sugar	10"	N.50°E.	11 links	(7.26 feet)
Sugar	5"	N.21°W.	11 links	(7.26 feet)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No evidence found of original corner, bearing trees or subsequent corner restoration.

Corner position re-established by single proportionate methods between the north quarter corner of section 6 and the northwest section corner of section 4; T.46N., R.42W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a standard 2½" diameter by 30" long split base aluminum monument with a 3" cast aluminum cap, Stamped to read: T.46-47N., R.42W.; ¼; S-5, S-32; 1992; R.L.S. 21564.

From which I have established the following new blazed and scribed bearing trees:

9"	Sugar Maple	N.15°E.	23.30 feet
12"	Hemlock	S.06°E.	28.40 feet
9"	Sugar Maple	S.68°W.	3.51 feet
6'	Steel rail	N.15°E.	2.3 feet

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY DATE

CHIEF OF SURVEY PARTY


APPROVED AND SIGNED BY

Richard L. Drahn
MICHIGAN REGISTERED LAND SURVEYOR

DATE 12-28-92

U.S.F.S. #A-7

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. 21564